

BEMIDJI REGIONAL AIRPORT (BJI) RUNWAY 13/31 REHABILITATION & STRENGTHENING PROJECT

MILLING RUNWAY 31 - JULY, 2023



PROJECT DESCRIPTION:

THE BEMIDJI REGIONAL AIRPORT - RUNWAY 13/31 REHABILITATION & STRENGTHENING PROJECT INCLUDED PROFILE MILLING THE RUNWAY BETWEEN 0" AND 2", AND RE-PAVING TWO NEW 2" LIFTS OF P-401 BITUMINOUS PAVEMENT. THIS GIVES RUNWAY 13/31 A TOTAL PAVEMENT THICKNESS OF 6" WHICH WILL ALLOW IT TO NOT ONLY SERVICE THE EXISTING FLEET MIX AT BJI, BUT ALLOW FOR FUTURE GROWTH AND EXPANSION WITHIN THE FLEET MIX. CONSTRUCTION BEGAN JULY 10TH, 2023 AND WAS COMPLETED BY SEPTEMBER 29TH, 2023. IN TOTAL, APPROXIMATELY 29,000 TONS OF BITUMINOUS WAS PLACED. KGM CONTRACTORS, INC. WAS ABLE TO SUCCESSFULLY COMPLETE THIS PROJECT ON SCHEDULE ALL WHILE MINIMIZING IMPACT TO AIR TRAFFIC AND COMMERCIAL SERVICE.

PAVING RUNWAY 13/31 & RUNWAY 7/25 INTERSECTION - JULY, 2023



MILLING RUNWAY 31 - JULY, 2023



RUNWAY 13/31 PAVED & PAINTED - SEPTEMBER 2023



NIGHTTIME RUNWAY GROOVING - SEPTEMBER, 2023



**TOTAL CONSTRUCTION COST
APPROXIMATELY \$4,424,000**

PROJECT RIBBON CUTTING - OCTOBER 2023

